

BULLI ROAD LANDSLIPS



Project: Bulli Road Landslips
Comboyne

Client: GTCC

Duration: 5 Weeks

Project Overview:

This project involved the following;

- ◆ Stabilisation of 2 landslips along Bulli Road, Comboyne.
- ◆ Installation of 232m of soil nails
- ◆ Backfilling against batter with no fines concrete.
- ◆ Installation of strip drains behind shotcrete facing
- ◆ installation of approx. 110 m² of reinforced shotcrete
- ◆ Works also included tree removal, scour protection at base of walls, scaling of batter faces, and placement of road base.

