

BUNNERUNGEE BRIDGES



Project: Bunnerungee Twin Bridges
Soil nailing and shotcreting

Client: RMS

Duration: 12 Days

Project Overview:

This project involved the following;

- ◆ Reinforced shotcrete applied to 4 abutments beneath and adjacent to twin bridges
- ◆ Installation of 882m of Soil nails
- ◆ This included 52 soil nails drilled through 4mm sheet piling.
- ◆ installation of strip drains behind shotcrete facing
- ◆ installation of approx. 400 m² of reinforced shotcrete
- ◆ Extensive environmental control of sensitive site containing river near abutments and Aboriginal artifacts.

