

Project: Putty Road Remediation Works

Client: RMS

Duration: 7 Months

PROJECT OVERVIEW

Warner won the contract with the RMS for the Putty Road Slope Remediation works and began work in April 2011. The project consisted of 21 separate job sites along a 50km stretch along the Northern end of Putty Road NSW.

The work Involved:

- Contracting the removal of over 1200 trees
- The scaling and removal of approximately 2200m³ metres of spoil
- The supply and installation of approximately 2500m of rockbolts and anchors
- The supply and installation of over 4000m² of Rockfall Protection Netting System (RPNS)

Due to limited access to some of the hole locations Warner used one of their excavator mounted drill rigs. This allowed the rig to be positioned on the road itself, and then drill over the embankment as shown in the first image.

