

Project: Ravensworth Underground Mine
Rail Loop Stabilisation

Client: Laing O'Rourke

Duration: 4 Months

PROJECT OVERVIEW

Warner Company began work in November 2011, completing over 4,700m of drilling and grouting works. In addition, Warner also completed approximately 4,500m² of shotcrete works to the batter of the Ravensworth Underground Mine/ Ravensworth Central Coal Processing Plant Rail Loop Cutting.

The works involved the:

- Scaling and removal of spoil
- Installation of dowels
- Installation of rockbolts
- The application of shotcrete
- Installation of rockfall netting

