

# WEBBER'S CREEK BRIDGE



**Project:** Webber's Creek Permanent Bridge Anchors

**Client:** RMS

**Duration:** 1 month

**Project Overview:**

This project involved the following;

- ◆ Traffic management
- ◆ Drilling of 22m deep, 152mm diameter holes from scaffold through bridge abutments
- ◆ Installation of permanent bridge anchors including testing and stressing
- ◆ Environmental control

The works involved difficult drilling conditions due to materials, access and environmental factors.

